HASSAN DIVISION.

The 24th March 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan division, up to 18th April 1898, for restoring the Chikka Gandasi tank, Registered No. 57, Arsikere taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Chikka Gandasi tank, Registered No. 57, Arsikere taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Hassan division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice-board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork to bund	C. yds.	17,642
Preparing and fixing new grade stones with bed slabs	Each.	55
Vis a Vis stones	Do	55
B. M. stones	Do	2
Register No. stone	Do	1
Gauge do	Do	1
Date do	Do	1
Turfing do	S. yds.	16,124
Rough stone work new jelly pitching	C. yds.	1,912
Do old	Do	739
Jelly wedging to crevices of old stone revetment	Do	311
Clearing jungle bund	Lump sum Rupees.	
Sluices—		
Examining and repairing sluice No. I	Lump sum Rupees.	
Do do No. II	Lump sum Rupees.	
Waste weirs—		
Waste weir left, 46′ length—		
Excavation	C. yds.	20
Burnt brick in surki mortar	C. ft.	366
Burnt stone slabs	S. ft.	94
Plastering with surki mortar	Sqrs.	2·31
Rough stone work new sujicut	C. yds.	150
Waste weir, right, 136 feet—		
Excavation	C. yds.	862
Burnt brick in surki mortar	C. ft.	1,504
Burnt stone slabs	S. ft.	392
Plastering with surki mortar	Sqrs.	2·31
Rough stone work sujicut	C. yds.	360
Supply—		
Repairing the feeder channel left	Lump sum Rupees.	
Do do right	Lump sum Rupees.	

A. S. NAGAVKAR, *Exec. Engineer.*

KOLAR DIVISION.

The 1st March 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar division, up to 15th April 1898 inclusive, for re-constructing Commandant's quarters, Commissioned Officer's quarters and huts for Barr sepoys stationed at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for re-constructing Commandant's quarters, Commissioned Officer's quarters and huts for Barr sepoys at Kolar, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities required for re-constructing Commandant's quarters Commissioned Officer's quarters and huts for Barr sepoys stationed at Kolar.

Items of work.	Per.	Quantities.					Total quantity.
		Commandant's qrs.		Five Commissioned officers quarters.	Six Barr sepoys huts.	Ashur Khana.	
		Main building.	Out houses.				
Dismantling the existing building and removing debris	L. S.	Rs. 100	..	...	...	...	Rs. 100
Compensation for site, &c. ...	,,	...	...	300	...	...	300
Dismantling the roof of existing old lines and removing debris	Sqr.	...	...	...	336·72	...	336·72
Dismantling the walls, existing old lines.	C. ft.	...	...	...	1,23,048	...	1,23,048
Earthwork excavation and filling basement	C. yds.	91	7	170	2,382	14	2,664
Filling foundation in concrete ...	C. ft.	...	...	...	3,726	...	3,726
Burnt stone in clay (filling foundation) ..	C. ft.	...	...	3,185	39,024	380	42,589
Burnt stone in chunam basement	C. ft.	2,231	196	1,425	24,888	228	29,018
Burnt brick in clay (superstructure) ..	C. ft.	2,568	598	4,970	1,06,826	941	1,15,913
Burnt brick in chunam cheeks of doors, &c.	C. ft.	974	82	1,550	16,800	[illegible]	[illegible]
Stone slabs	S. ft.	274	8	645	8,346	[illegible]	[illegible]
Flooring with Mangalore square tiles over 3" concrete bed	Sqr.	9·26	...	...	..	...	9·26
Flooring gravel	C. yds.	....	2	60	600	5	667
Do slabs and cement pointing ...	Sqr.	..	...	1·50	42·00	...	43·50
Chunam plastering (fine)... ...	,,	18·44	5·8	26·20	263·04	8·14	321·62
Do do (rough)	,,	....	...	34·85	916·14	...	950·99
Chunam pointing basement	,,	2·22	1·00	4·30	48·69	1·28	56·77
Mud plastering interior	,,	31·30	2·12	73·20	1,094·82	6·04	1,208·78
White washing	,,	31·30	..	73·20	1,11[illegible] 0	6·74	1,121·24
Color washing	,,	18·14	..	34·85	916·14	7·74	977·17
Horne wood work	C. ft.	101·44	10·20	148·05	2,544 00	52·31	2,856·03
Roofing with 1st class Mangalore tiles and teak reepers, complete ...	Sqr.	17·40	1·0	31·40	417 60	5·98	477·23
Ridge tiles set in mortar	R. ft.	40	17	110	1,044	23	1,234
Ventilating tiles	No.	10	...	40	576	...	626
Horne wood doors, pannelled ..	S. ft.	180	18	540	6,984	...	7,722
Do windows, pannelled ...	S. ft.	72	...	60	1,080	...	1,212
Eave board ornamental	R. ft.	80	...	...	...	...	80
Cornice plain over gables	,,	78	40	...	468	31	617
Coping with brick in chunam, and chunam plastering	,,	...	...	210	6,972	...	7,182
V-shaped drains, uncovered ...	,,	...	...	220	2,922	...	3,142
Do covered ...	,,	...	...	...	240	...	240
Main drain into which all the drains round the huts, &c., empty ...	will discharge L. S. B.				192	...	192
Tarring	Sqr.	...	...	...	223·14	...	223·14
Wood oiling	,,	6·66	1·33	...	157·56	2·00	167 55
Horne wood pegs with tarring, &c. ..	No	10	...	50	720	...	780
Painting doors and windows ...	Sqr.	6·65	...	15·55	165·60	...	187·80
Wood oiling, tarring, plain cornice, dwarf wall, end wall, plastering, painting, &c.				L. S.	150	...	150